


15-137-00243-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Norton County. Sec. 12 Twp. 2 Rge. 25 (X) (W)  
Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Herman Geo. Kaiser, et al  
Lease Name Strayer Well No. 1  
Office Address 909 Palace Bldg. Tulsa, Okla.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Jan. 1, 1957 19  
Application for plugging filed Jan. 1, 1957 19  
Application for plugging approved Jan. 1, 1957 19  
Plugging commenced Jan. 1, 1957 19  
Plugging completed Jan. 1, 1957 19  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3769 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	212'	cemented w/135 sks.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 200', bottom plug set at 200' with 1/2 sack hulls, 15 sacks cement; mud to 40', top plug with 1/2 sack hulls, 10 sacks cement, cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Veeder Supply and Development Co.  
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.  
C. H. Woods (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) C. H. Woods  
Cherryvale, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of January, 1957

My commission expires July 11, 1960.  
Eldon Lawson Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION  
PLUGGING CONSERVATION DIVISION  
Wichita, Kansas  
FILE SEC 12 T. 2 R. 25W  
BOOK PAGE 131 LINE 38  
1-15-57

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Herman Geo. Kaiser-Francis Oil & Gas Farm Strayer No. 1 Depth 3769'  
 Contractor Veeder Supply & Development Co. Pipe 212' 8 5/8" csg w/135 sacks 2% CC  
 Location SE/4 SE/4 SW/4 Sec. 12 Twp. 2 Range 25W  
 Commenced 12-19-1956 Completed 1-1-1957 County Norton State Kansas

Cellar	0	9	9
Clay and shale	9	50	41
Shale	50	140	90
Sand and shale	140	185	45
Shale	185	425	240
Shale shells	425	610	185
Shale	610	1190	580
Shale sand	1190	1690	500
Sand	1690	1750	60
Sand, shale, red bed	1750	2031	281
Anhydrite	2031	2065	34
Shale shells	2065	2286	221
Shale and lime streaks	2286	2535	249
Lime shale	2535	2840	305
Shale lime	2840	3060	220
Lime and shale	3060	3142	82
Shale lime	3142	3175	33
Lime shale	3175	3365	190
Lime	3365	3709	344
Shale lime sand	3709	3762	53
Granite wash	3762	3769	7
T. D.	3769		

Dry and abandoned.

AFFIDAVIT

STATE OF KANSAS )  
Montgomery County) SS

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above drilling log covering the Strayer #1 well located in Section 12-2-25W-Norton County, Kansas, and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By C. H. Woods  
C. H. Woods

Subscribed and sworn to before me this 4th day of January, 1957.

Charles Lamson  
Notary Public

My commission expires July 11, 1960.

**RECEIVED**  
STATE CORPORATION COMMISSION

PLUGGING 25W  
 SEC 12 T 2 R  
 121 11-38  
 CONSERVATION DIVISION  
 Wichita, Kansas

1-15-57