


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-137-00175-00-00

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Norton County, Sec. 1 Twp. 2S Rge. 24 (E) (W) **x**

Location as "NE/CNW%SW%" or footage from lines SE SE SE
Lease Owner Empire Drilling Company AND R. W. Shields
Lease Name Meier "A" Well No. 1
Office Address 650 Fourth National Bank Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 8, 1961 19
Application for plugging filed April 8, 1961 19
Application for plugging approved April 8, 1961 19
Plugging commenced April 8, 1961 19
Plugging completed April 8, 1961 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3745 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Shale	0	247	8 5/8"	216'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set at 400' with 20 sacks cement.
Plug set at 210' with 20 sacks cement.
Plug set at 40' with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1961

CONSERVATION DIVISION
Wichita, Kansas

4-25-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Empire Drilling Company
Address 650 Fourth National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Dan J. Kornfeld ~~employee of owner~~ (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
650 Fourth National Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of April, 19 61

My commission expires April 23, 1965 Effie I. Foote Notary Public.



15-137-00175-00-00

LOG

COMPANY: Empire Drilling Company and R. W. Shields
 CONTRACTOR: Empire Drilling Company
 FARM: Meier "A" # 1
 LOCATION: SE SE SE Section 1-2S-24W, Norton County, Kansas
 COMMENCED: March 28, 1961
 COMPLETED: April 8, 1961
 ELEVATION: 2467 KB
 POTENTIAL: D & A

0	to	247	Shale
247	to	1630	Shale-Shells
1630	to	1730	Sand
1730	to	1795	Shale
1795	to	2011	Shale-Shells
2011	to	2038	Anhydrite
2038	to	2540	Shale
2540	to	2735	Shale-Lime
2735	to	3395	Lime-Shale
3395	to	3475	Lime
3475	to	3570	Lime-Shale
3570	to	3630	Lime
3630	to	3690	Lime-Shale
3690	to	3745	Shale-Lime
3745			Rotary Total Depth

SET: 216 8 5/8" casing with 115 sacks cement.


ELECTRIC LOG TOPS:

Heebner	3414	-947
Toronto	3446	-979
Lansing	3460	-993
Base Kansas City	3648	-1181
Arbuckle	3709	-1242
Reagan Sand	3732	-1265
Granite Wash	3736	-1269
Granite	3746	-1279
Welex Total Depth	3747	

RECEIVED
 STATE INFORMATION COMMISSION
 APR 25 1961
 CONSERVATION DIVISION
 Wichita, Kansas
 4-25-61

CERTIFICATION

I, Dan J. Kornfeld, do hereby certify that the above and foregoing is a true and correct copy of the log on the Meier "A" # 1, SE SE SE Sec. 1-2S-24W, Norton County, Kansas, as reflected by the files of Empire Drilling Company.


 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 24th day of April, 1961.


 Effie I. Foote, Notary Public

My commission expires April 23, 1965.