

15-137-20186-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Norton SEC. 29 TWP. 2s RGE. 24w E/W
 Location as in quarters or footage from lines:
710' FWL & 810' FNL

Locate Well
 correctly on above
 Section Platt.

Lease Owner Hummon Corporation
 Lease Name Wegener #3 Well No. _____
 Office Address 400 One Main Place, Wichita, Kansas 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 12/10/82
 Plugging completed 12/14/82
 Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hammel
 Producing formation _____ Depth to top _____ bottom _____ T.D. 3814'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	270'	none
				4 1/2"	3806'	802'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Plugged bottom with 4 sacks cement, sand to 3400' & 4 sacks cement.
Shot well at 2523', 2006', 1534', 1302', 1226', 1016', 919', & 814'.
Pulled 19 joints. Plugged well with 15 sacks gel, 4 sacks hull, 50
cement, 100 cement with 2 hulls, 15 gel, plug, & 75 cement with 2 hulls.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of December, 19 82



Irene Hoover
 STATE OF KANSAS Notary Public.

My Commission expires:

DEC 30 1982

CONSERVATION DIVISION
 Wichita, Kansas

12-30-82

DRILLERS LOG

No. 3 Wegener

15-137-20186-0000

CASING RECORD:

COMPANY: Hurmon Corporation

DESCRIPTION:

8 5/8" @ 270'
w/180 sx cement

CONTRACTOR: Red Tiger Drilling Company

C NW/4 NW/4
Sec. 29-T2S-R24W
Norton County, Kansas

4 1/2" @ 3,806'
w/150 sx cement

COMMENCED: August 22, 1980

COMPLETED: September 2, 1980

TOTAL DEPTH: 3,814'

ELEVATION: 2,502' KB

FORMATION

FROM

TO

REMARKS

Shale, Sand & Shale	0	280	
Shale	280	870	
Shale, Sand & Shale	870	1517	
Shale	1517	1646	
Sand	1646	1798	
Shale	1798	2033	
Anhydrite	2033	2064	
Shale	2064	2122	
Shale (Lime Streaks)	2122	2615	
Lime & Shale	2615	2865	
Shale & Lime	2865	2998	
Lime	2998	3814	
RTD		3814	

STATE RECEIVED
DEC 3 1982
CONSERVATION DIVISION
Wichita, Kansas

12-3-82

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 8th day of September, 1980.

Joyce A. Hagermann
Notary Public

