

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

#4 API NUMBER 15-137-20,179 00-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME Foley

WELL NUMBER 1

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 29 TWP. 2S RGE. 24 ~~XXX~~ (W)

COUNTY Norton

Date Well Completed 10/17/80

Plugging Commenced 10/11/88

Plugging Completed 10/12/88

LEASE OPERATOR Hummon Corporation

ADDRESS 400 One Main Place, Wichita, KS 67202

PHONE#(316) 263-8521 OPERATORS LICENSE NO. 5050

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 11, 1988 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? C-10 If not, is well log attached? \_\_\_\_\_

Producing Formation Reagan SD Depth to Top 3762 Bottom 3773 T.D. 3801

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR ~~WATER~~ RECORDS 11-7-88 CASING RECORD

Formation	Cont	From	To	Size	Put in	Pulled out
<u>154</u>	<u>11-7-88</u>			<u>8-5/8"</u>	<u>273'</u>	<u>NONE</u>
				<u>4 1/2"</u>	<u>3820'</u>	<u>NONE</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.  
Dump 150 gals of sand down hole with water, hit bridge @ 2000'. Shot hole @ 1250' and 3 holes @ 2000'. Ran 68 jts of 2-3/8" tbg. to 2166'. Circulated & cement around tbg. and csg. Pull tbg out, cement w/150sx. common & 100sx Poz., 2% Gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe Servicing, Inc. License No. 3152

Address Box 115, Oberlin, KS 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hummon Corporation

STATE OF Kansas COUNTY OF Sedgwick, ss.

Byron E. Hummon, Jr.

(XXXXXXXXXXXXXXXXXXXX or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Byron E. Hummon, Jr.

(Address) 400 One Main Place, Wichita, KS



SUBSCRIBED AND SWORN TO before me this 15th day of November, 19 88

Sandra L. Mendoza  
Notary Public

My Commission Expires: February 13, 1990

DRILLERS LOG

15-137-20179-00-00

No. 1 Foley

## CASING RECORD:

8 5/8" @ 280'  
w/185 sx cement4 1/2" @ 3,816'  
w/150 sx cement

TOTAL DEPTH: 3,821'

COMPANY: Hummon Corporation

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: May 22, 1980

COMPLETED: May 31, 1980

## DESCRIPTION:

50' S of C NW/4 SW/4  
Sec. 29-T2S-R24W  
Norton County, Kansas

ELEVATION: 2,502' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Shale	0	283	
Shale & Clay	283	665	
Shale	665	1174	
Sand	1174	1284	
Iron Pyrite	1284	1289	
Shale & Sand	1289	1570	
Shale & Red Bed	1570	1700	
Sand	1700	1795	
Shale & Red Bed	1795	2045	
Anhydrite	2045	2074	
Shale	2074	2080	
Shale & Red Bed	2080	2350	
Shale & Lime Streaks	2350	2640	
Lime	2640	3771	
Granite Wash	3771	3821	
RTD		3821	


Coring 3742 - 3771

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

  
Gloria Fawcett

Subscribed and sworn to before me this 4th day of June, 1980.

  
Notary Public