

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

18-137-20157-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Norton SEC. 35 TWP. 2S RGE. 24W E/W  
 Location as in quarters or footage from lines:  
C NW SE


Lease Owner Hummon Corporation  
 Lease Name Smith #1 Well No. \_\_\_\_\_  
 Office Address 400 One Main Place Wichita, Ks. 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 6-15-82  
 Plugging completed 6-17-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

\_\_\_\_\_ Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3720'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	259'	none
				4-1/2"	3662'	1086'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Ran 50' of sand and 4 sacks cement and pushed bottom plug to 3400'. Shot casing @2011', 1707', 1416', and 1094'. Pulled a total of 27 joints of 4-1/2" casing. Plugged well with 3 sacks hulls, 13 sacks gel, 2 sacks hulls, 70 sacks 50/50 pos 6% gel 3% cc, 12 sacks gel, released plug and displaced with 70 sacks 50/50 pos 6% gel 3% cc.

Plugging Complete.


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of June, 1982



RECEIVED  
 STATE CORPORATION COMMISSION  
[Signature]  
 Notary Public.

My Commission expires: \_\_\_\_\_

JUN 24 1982

CONSERVATION DIVISION  
 Wichita, Kansas

6-24-82

Hummon Corporation  
400 One Main Place  
Wichita, Kansas 67202

Smith #1  
C NW SE Sec. 35-25-24W  
Norton County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
221 S. Broadway, Suite 400  
Wichita, Kansas 67202

Commenced: October 26, 1979  
Completed: November 2, 1979

Drillers Log

Shale & Sand	138
Chert	152
Shale	720
Blue Shale	1615
Sand	1732
Shale	1750
Shale & Shells	1985
Anhydrite	2014
Shale & Shells	2625
Shale & Lime	3455
Lime	3500
Lime & Shale	3611
Lime	3670
Lime & Sand	3720 RTD