


STATE OF KANSAS  
STATE CORPORATION COMMISSION

15-137-00246-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Norton County. Sec. 20 Twp. 2 Rge. 24 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NENE SE  
Lease Owner D. G. Hansen  
Lease Name Duensing Well No. 1  
Office Address Logan, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 20 19 56  
Application for plugging filed November 20 19 56  
Application for plugging approved November 20 19 56  
Plugging commenced November 21 19 56  
Plugging completed November 21 19 56  
Reason for abandonment of well or producing formation Too low structually

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty Hays, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3775 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	295'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 290'. Set plug. Put in 1/2 sack Hulls & 15 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1/2 sack Hulls and 15 sacks Cement.

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

11-28-56

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.  
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
G. F. Galloway (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway  
107 Rule Building  
(Address)

SUBSCRIBED AND SWORN to before me this 26th day of November, 1956

My commission expires May 20, 1959

Vicky Jacobs  
Vicky Jacobs Notary Public.

PLUGGING  
FILE SEC 20 T. 2 R. 24W  
BOOK PAGE 119 LINE 29

15-137-00246-00-00

CONTRACTOR'S WELL LOG

OPERATOR D. G. HANSEN WELL NAME DUENSING #1

LOCATION NE NE SE SECTION 20-2-24W RIG NO. 1

COUNTY NORTON STATE KANSAS

COMMENCEMENT DATE NOVEMBER 13, 1956 COMPLETION DATE NOVEMBER 20, 1956

LOG OF WELL

Elevation 2500' rotary bushing.  
 All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS
0	295	Surface Soil		
295	700	Shale		
700	1150	Sand-Shale		
1150	2000	Sand-Shale		
2000	2025	Red Bed		
2025	2060	Anhydrite		
2060	2300	Shale		
2300	2575	Lime-Shale	0° - 2500	
2575	2825	Shale-Lime	0° - 2750	
2825	2945	Lime-Shale		
2945	3105	Lime-Shale	0° - 3000	
3105	3305	Lime-Shale	0° - 3250	
3305	3495	Lime-Shale		
3495	3560	Lime-Shale	0° - 3500	DST 3476' to 3515'
3560	3635	Lime-Shale		DST 3607' to 3635'
3635	3775	Lime-Shale	0° - 3750	

CASING LEFT IN HOLE AFTER COMPLETION

Set 295' of 8-5/8" OD Surface Casing (14 jts.)

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } SS.

STATE OF KANSAS  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 11-24-56

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By G. F. Galloway  
 G. F. Galloway

Subscribed and sworn to before me this 26th day of November, 1956.

My commission expires:  
May 20, 1959

Vicky Jacobs  
 Vicky Jacobs, Notary Public

PLUGGING  
 FILE SEC 20 T. 2 R. 24W  
 BOOK PAGE 119 LINE 29