

15-147-00719-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER N/A

LEASE NAME Dayton Unit

WELL NUMBER #5 Injection Well

SPOT LOCATION 75' W of C NE NE

SEC. 35 TWP. 2S RGE. 19W (K) or (W)

COUNTY Phillips

Date Well Completed 8-11-61

Plugging Commenced 1-15-85

Plugging Completed 1-15-85

LEASE OPERATOR Sierra Petroleum Co., Inc.

ADDRESS P. O. Box 247, Wichita, Kansas 67201

PHONE # (316) 264-8394 OPERATORS LICENSE NO. 5064

Character of Well Input
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? No If not, is well log attached? Not available.

Producing formation N/A Depth to top - bottom - T.D. 3385'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	314'	none
				4-1/2"	3450'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mixed down casing 20 sacks cement without hulls and 230 sacks with hulls at 1000# psi. Shut in at 800 PSI. Hooked up to back side and mixed 225 sacks cement with 2 sacks hulls. Maximum 400# PSI mixing pressure. Shut in at 100# PSI at 1:15 PM. Used a total of 475 sacks 50/50 poz mix, 10% gel with 1/4# Floseal and hulls.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sierra Petroleum Co., Inc. License No. 5064
Address P. O. Box 247, Wichita, Kansas 67201

RECEIVED 5064
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Sedgwick, ss.


Jack L. Yinger, Vice President (employee of operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack L. Yinger
(Address) P. O. Box 247, Wichita, Ks. 67201

SUBSCRIBED AND SWORN TO before me this 8th day of February, 1985

Aldine M. Johnson
Notary Public

My Commission expires: ALDINE M. JOHNSON



Form CP-4 1-84
Revised 06-83