

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-147-20,342-00-00

LEASE NAME KAISER

WELL NUMBER 1

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 25 TWP. 2S RGE. 19W (E) or (W)

COUNTY Phillips

Date Well Completed 9/2/81

Plugging Commenced 2/22/95

Plugging Completed 2/27/95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Graham-Michaelis Corp.

ADDRESS P. O. Box 247, Wichita, KS 67201

PHONE#(316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 16, 1995 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top 3253' Bottom 3588' T.D. 3588'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	270'	0
				4-1/2"	3585'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Moved in LK Wireline to perforate 4-1/2" casing. Shot two holes @ 1150' and two holes @ 1650'.
Moved in Allied Cementing, Inc. Pressured up on backside between 8-5/8" & 4-1/2" casing.
Pressured to 500# PSI. Tied onto 4-1/2" casing & started mixing 300 sacks 60/40 poz mix with 8% gel and 500# hulls. Mixed all of the cement. No Pressure. Took Reinhardt Services to run wireline. Cemented down to 678'. Ordered 3 yards Ready-MIX. Filled casing to surface.

Name of Plugging Contractor Graham-Michaelis Corp. License No. 5134

Address P. O. Box 247, Wichita, KS 67201

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Yinger, Vice President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Jack L. Yinger

(Address) P.O.Box 247, Wichita, KS 67201

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1995

Aldine M. Johnson
Notary Public

My Commission Expires:



STATE CORPORATION COMMISSION
MAR 16 1995
376-95
WICHITA, KANSAS