


15-147-30174-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail & Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Phillips County. Sec. 33 Twp. 2S Rge. (E) 19 (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SW 1/4 SW 1/4 SE 1/4  
Lease Owner Barnett Oil Company, et al  
Lease Name Krafft Well No. 1  
Office Address 417 First National Bank Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed October 3 1950  
Application for plugging filed October 3 1950  
Application for plugging approved October 3 1950  
Plugging commenced October 3 1950  
Plugging completed October 3 1950  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 3676 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Casing				8 5/8"	188 ft.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3676 feet to 180 feet. Set wooden plug at 180 feet and filled casing with cement to 133 feet. Filled casing with heavy mud from 133 feet to 35 feet. Set wooden plug at 35 feet and filled casing with cement to bottom of cellar.


RECEIVED  
STATE CORPORATION COMMISSION  
OCT 24 1950  
CONSERVATION DIVISION  
Wichita, Kansas  
10-24-50

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to Barnett Oil Company  
Address 417 First Nat'l. Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. R. Hunter (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) W. R. Hunter  
First Nat'l. Bank Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 1950.  
Adelaide Oliver Notary Public.

My commission expires May 12, 1951 22-7377-s 4-49-10M



BARNETT OIL COMPANY, ET AL

LOG OF KRAFFT WELL NO. 1

SW $\frac{1}{4}$  SW $\frac{1}{4}$  SE $\frac{1}{4}$  SECTION 33-2S-19W, PHILLIPS COUNTY, KANSAS

COMMENCED: September 22, 1950

COMPLETED: October 3, 1950

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Shale	0	95	
Sand	95	135	
Shale	135	188	Set 8 5/8" Surface Pipe at 188 Ft. Cemented with 150 Sacks.
Shale and Shells	188	950	
Sand and Shale	950	1175	
Sand	1175	1375	
Shale and Shells	1375	1670	
Anhydrite	1670	1700	
Shale and Shells	1700	2210	
Lime and Shale	2210	2275	
Shale and Shells	2275	2360	
Lime	2360	2390	
Shale and Lime	2390	2580	
Lime	2580	2655	
Lime and Shale	2655	3170	
Lime	3170	3250	
Lime and Shale	3250	3305	
Lime	3305	3520	
Lime and Shale	3520	3660	
Lime	3660	3676	
Total Depth		3676	Dry and Abandoned.

Certificate

I, W. R. Hunter, Office Manager of the Barnett Oil Company, hereby certify that to the best of my knowledge and belief the above is a true and correct log of the Krafft Well No. 1, located in the SW $\frac{1}{4}$  SW $\frac{1}{4}$  SE $\frac{1}{4}$  of Section 33-2S-19W, Phillips County, Kansas.

*W. R. Hunter*

Subscribed and sworn to before me, a Notary Public in and for the County of Sedgwick, State of Kansas, this 16th day of October, 1950.

*Adelaide Olivier*  
Notary Public.

My commission expires May 12, 1951.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 24 1950  
CONSERVATION DIVISION  
Wichita, Kansas  
10-24-50

PLUGGING  
FILE SEC 33 T 2 R 19W  
BOOK PAGE 33 LINE 7