


15-147-19072-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Phillips County, Sec. 26 Twp. 2S Rge. (E) 19 (W)

Location as "NE/CNW/SW" or footage from lines NE 1/4 SW 1/4 SE 1/4

Lease Owner Horizon Oil Company - Lewis Drilling Company

Lease Name Friebus Well No. 1

Office Address 915 Union Center Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed September 25 1958

Application for plugging filed September 24 1958

Application for plugging approved September 25 1958

Plugging commenced September 25 1958

Plugging completed September 25 1958

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 247' | -0- |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud, run bottom plug to 500' cemented through drill pipe with 10 sacks cement. Set second plug at 180' with 10 sacks cement. Set top plug at 40' with 10 sacks cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company

Address 915 Union Center Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

William J. Duckett (employee of owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William J. Duckett

915 Union Center Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of October, 1958

My commission expires August 20, 1960 A. R. Derrington Notary Public.



OCT 25 1958
CONSERVATION DIVISION
KANSAS

PLUGGING
FILE SEC 26 T 2 R 19W
BOOK PAGE 134 LINE 34

10-23-58

15-147-19072-00-00

WELL LOG

COMPANY Horizon Oil Company - Lewis Drilling Company

SEC. 26 T. 2S R. 19W

FARM Friebus

NO. 1

LOC. NE 1/4 SW 1/4 SE 1/4

TOTAL DEPTH 3500'

COMM. September 16, 1958

COMP. September 25, 1958


COUNTY Phillips

KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

| | |
|----|---------------|
| 20 | 10 |
| 15 | 8-5/8" - 247' |
| 12 | 6 |
| 13 | 5 |

ELEVATION 2126 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

| | |
|-------------|-------------------------------|
| 0 - 180 | Clay & Shale |
| 180 - 1510 | Shale |
| 1510 - 1595 | Shale & Shells |
| 1595 - 1625 | Anhydrite |
| 1625 - 2005 | Shale & Shells W/Lime Streaks |
| 2005 - 3180 | Lime & Shale |
| 3180 - 3250 | Lime |
| 3250 - 3407 | Lime & Shale |
| 3407 - 3500 | Lime |
| 3500 - | Total Depth |

Geologic Tops

| | |
|---------|------|
| Heebner | 3203 |
| Toronto | 3227 |
| K C | 3244 |

STATE OF KANSAS
DEPARTMENT OF GEOLOGY

OCT 23 1958

CONSERVATION DIVISION
Wichita, Kansas

10-23-58

PLUGGING
FILE SEC 26 T. 2 R. 19W
BOOK PAGE 134 LINE 34

State of Kansas
County of Sedgwick

ss:

I, William J. Duckett of the Lewis Drilling Company upon oath state that the above and foregoing is a true and correct copy of the log of the Friebus #1 well.

William J. Duckett

Subscribed and sworn to before me this 22nd day of October 1958

My Commission Expires: August 20, 1960

A. R. Derrington
NOTARY PUBLIC
(A. R. Derrington)