

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-04876-00-00  
Spot: NENWNW Sec/Twnshp/Rge: 22-11S-18W  
4950 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: DEAN Well #: 4  
County: ELLIS Total Vertical Depth: 3491 feet

Operator License No.: 5386  
Op Name: PRODUCTION DRILLING, INC.  
Address: PO BOX 680  
HAYS, KS 67601

PROD Size: 5.5 feet: 3481 125 SX CMT  
SURF Size: 8.62 feet: 122 80 SX CMT

#1344

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/15/2000 12:00 PM  
Plug Co. License No.: 5386 Plug Co. Name: PRODUCTION DRILLING, INC.  
Proposal Rcvd. from: AVEN WEAVERLING Company: PRODUCTION DRILLING, INC. Phone: (785) 625-1189

Proposed D.V. Tool at 1288' w/600 sxs.  
Plugging Dakota 336' - 636'. Anhy. 1240' - 1280'. Salt 1592' - 1802'.  
Method: Fluid Level at 500'. Top of tubing fish at 3000'.  
Ordered out 340 sxs 60/40 pozmix - 10% gel with 500# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/15/2000 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 2870'. Allied pumped 40 sxs 60/40 pozmix - 10% gel, followed with 60 sxs 60/40 pozmix - 10% gel with 300# hulls.  
Pulled tubing to 1800' and Allied pumped 110 sxs with 100# hulls. Circulated cement. PTOH. Hooked up to 5 1/2" casing annulus. Pumped 50 sxs cement with 100# hulls.  
Max. P.S.I. 200#. S.I.P. 100#.  
Allied ran out of cement, instead of 340 sxs cement, brought out 260 sxs. 80 sxs short. Cement in 5 1/2" casing stayin at 350' from surface.  
December 18,2000 - Cement at 350'. Ordered out 6 yards of Redi-Mix and topped off casing.

Remarks: ALLIED CEMENTING COMPANY

Plugged through: TBG

District: 04

INVOICED

Signed Richard Williams by Herb Deines (TECHNICIAN) District Supervisor.

DATE 1-1-04  
WILLIAMS RECEIVED 12/15/2000  
Amended  
CP 2/3

RECEIVED

JUN 21 2004

KCC WICHITA

JUN 16 2004

H H BLAIR

#4

DEAN

22-1-18W

NE NW NW

Contr.

ELLIS

County

E 1936

Comm. 6-1-48

Comp. 7-23-48

IP 300 BOPD PHY POT

Tops	Depth	Datum	Casing
ANH	1240	+696	8" 145 SWB 12 BOPH 5" 3485
TOP	2900	-964	
HEEB	3126	-1190	
LANS	3168	-1232	
B/KC	3401	-1463	
CONG	3430	-1494	
ARB	3485	-1549	✓
T.D.	3492	-1556	


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS