

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01976-00-01
Spot: NWSWSE Sec/Twnshp/Rge: 28-13S-14W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: ERHLICH Well #: 1
County: RUSSELL Total Vertical Depth: 3286 feet

Operator License No.: 31428
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL
Address: PO BOX 417
VICTORIA, KS 67671

PROD Size: 5.5 feet: 3285
SURF Size: 8.625 feet: 172

106⁸⁰

Well Type: SWD UIC Docket No: D19772.0 Date/Time to Plug: 06/07/2004 9:00 AM
Plug Co. License No.: 3232 Plug Co. Name: LIGHTNING WELL SERVICE, INC.
Proposal Rcvd. from: JEFF CRAWFORD Company: LONESTAR OIL COMPANY Phone: (785) 735-2725

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/07/2004 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran tubing to 2800'.
Pumped 100 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 1400'.
Circulated with 90 sxs cement and 200# hulls.
POOH.
Tied onto 5 1/2" and pumped 50 sxs cement.
Max. P.S.I. 600#. S.I.P. 300#.
Pressured backside to 300# P.S.I.
Well was squeezed at 350' w/100 sxs cement.

RECEIVED
JUN 21 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED

DATE 6-21-04

TEL. NO. 2004012764

Form CP-2/3

JUN 17 2004

~~DATE~~

~~DATE~~

INVOICE

KIM OIL

#1 EHRlich

28-13-14W
NW SW SE

Contr. MAST DRILLING RUSSELL County


E 1867RB Comm. 7-23-54 Comp. 8-27-54 IP 25 BOPD

Tops	Depth	Datum
KC	3020	-1153
ARB	3283	-1416
TD	3286	-1419

Casing
5" 3285

CO 3286: ACID 500.

ATHERTON POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS