

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-04804-00-00
Spot: NESWSW Sec/Twnshp/Rge: 30-13S-14W
990 feet from S Section Line, 4290 feet from E Section Line
Lease Name: ATHERTON B Well #: 2
County: RUSSELL Total Vertical Depth: 3560 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

L1 Size: 4.5 feet: 3561 w/50 sxs cmt
PROD Size: 5.5 feet: 3282 w/50 sxs cmt
SURF Size: 8.625 feet: 920 w/200 sxs cmt

Well Type: SWD UIC Docket No: D06190.0 Date/Time to Plug: 06/14/2004 10:00 AM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2004 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Perforated casing at 1625' - 930' - 450'.
Hooked up to the annulus - mixed and pumped 100 sxs cement - circulating cement up 5 1/2" - shut in.
TIH with tubing to 1700' - tied onto and circulated cement up 4 1/2" with 85 sxs cement and 600# hulls.
POOH and topped with 65 sxs cement.
Hole full of cement.


RECEIVED
JUN 21 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

JUN 16 2004

SHIELDS OIL PRODUCERS

#2

ATHERTON 'B'

30-13-14W
NE SW SW

Contr. SHIELDS DRLG

RUSSELL

County

El 853 RB

Comm.

11-30-57

Comp.

1-10-58

IP

S W D W

| Tops | Depth | Datum |
|------|-------|-------|
| HEEB | 2962 | -1109 |
| | | |
| LANS | 3012 | -1159 |
| | | |
| | | |
| ARB | 3280 | -1427 |
| | | |
| TD | 3560 | -1707 |

Casing

8" 920 w 200 SXS

5" 3282 w 50 SXS

CORRECTED CARD

1-31-58

DST. 3050-56/1 HR, 120' SW

BHP 735#

CO: SQZ: CD 3560

GORHAM POOL

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

(CORR ELEVATION, TD
& DATUM)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS