

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21188-00-00
Spot: S2SESWNW Sec/Twnshp/Rge: 27-12S-16W
2870 feet from S Section Line, 4290 feet from E Section Line
Lease Name: FROELICH B J I & H Well #: 6
County: ELLIS Total Vertical Depth: 3602 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO.
Address: 140 WEST WICHITA AVE.
RUSSELL, KS 67665

PROD Size: 4.5 feet: 3590 w/125 sxs cmt
SURF Size: 8.625 feet: 205 w/150 sxs cmt

A 117.07

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/04/2004 9:00 AM
Plug Co. License No.: 31172 Plug Co. Name: L & M WELL SERVICING, INC.
Proposal Rcvd. from: ARNOLD MICHAELIS Company: BENNETT & SCHULTE OIL COMPA Phone: (785) 483-2721

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2004 11:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran tubing to 1380'. Stacked out.
Circulated with 70 sxs 60/40 pozmix - 10% gel cement with 200# hulls.
POOH.
Tied onto 4 1/2" and pumped 70 sxs cement.
Max. P.S.I. 600#. S.I.P. 400#.
Tied onto backside and pumped 75 sxs cement with 200# hulls.
Max. P.S.I. 400#. S.I.P. 200#.

RECEIVED
JUN 21 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

160

Signed *Case Morris*
(TECHNICIAN)

INVOICED

Form CP-2/3

JUN 17 2004

DATE 6.21.04
REV. NO. 2004061757

HAYNES OIL CO.
 BOX 329, RUSSELL, KS. #6 J. J. & H. FROELICH "B" 27-12-16W
 100'S, SE SW NW

CONTR SHIELDS DRLG. CO., INC. CTY ELLIS
 GEOL FIELD EMMERAM

E 2122 KB: CM 6/21/76 CARD ISSUED 7/22/76 IP P 25 BOPD, NW
 LANS 3411-88

	+	+
	+	+

API 15-051-21,188

SMP	TOPS	DEPTH	DATUM
HEEB		3278	-1156
LANS		3329	-1207
RTD		3602	-1480

8 5/8" 205/150sx, 4 1/2" 3590/125sx
 NO DST'S
 MICT - PF 3411-88, AC 3000, SWB LD, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MAILED

JUL 27 1976