

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07208-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 2-14S-15W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: ROUBACK Well #: 9
County: RUSSELL Total Vertical Depth: 3292 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 804, LB 30
DALLAS, TX 75205

PROD Size: 5.5 feet: 3290
SURF Size: 10 feet: 923

99
106

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/02/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ALAN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (214) 219-8883

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/02/2004 12:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Well was squeezed at 470' w/100 sxs and 498' w/100 sxs in 1950.
Ran tubing to 2000'.
Circulated with 260 sxs 60/40 pozmix - 10% gel cement with 700# hulls.
POOH.
Pumped 140 sxs cement with 100# hulls.
Max. P.S.I. 350#. S.I.P. 200#.

RECEIVED
JUN 21 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Case Morris
(TECHNICIAN)

INVOICED
DATE: 6-21-04
INV. NO. 2004061765

JUN 17 2004

NOTHING TO REPORT
DATE 11-1-37
11/1/37

HARTMAN-BLAIR OIL CO #9 ROUBACK 2-14-15W
NW SW NW

Contr. RUSSELL County

E 1875 Comm. 6-12-37 Comp. 7-24-37 IP 1625 BOPD

K. C. C. Wichita Fax: 316-337-6211

Tops	Depth	Datum	Casing
ANHY	916		5" 3290
LANS	3039		
ARB	3290		
TD	3292		

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS
