

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21809-00-00
Spot: NENESE Sec/Twnshp/Rge: 25-28S-8W
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: GILLEN Well #: A1
County: KINGMAN Total Vertical Depth: 4497 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S. MAIN ST.
KINGMAN, KS 67068

PROD Size: 4.5 feet: 4497 125 SX CMT
SURF Size: 8.625 feet: 220 150 SX CMT

\$146¹⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/28/2004 1:30 PM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Perfs 3618'-3624'; 4053'-4057'; 4206'-4209'.
Plugging Sand to 3570' & 4 sxs; rec pipe; 1150' & 35 sxs; 750' & 35 sxs; 250' - 0' circ.
Method: Rec 3260'.

**RECEIVED
KCC DISTRICT #2
JUN - 7 2004
WICHITA, KS**

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 05/28/2004 1:30 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand to 3570' and capped with 4 sacks of cement. The casing was recovered from 3260', pulled to 1150', and spotted 35 sacks of cement. Pulled to 750' and spotted 35 sacks of cement. Pulled casing to 270' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
4206	4209		
4053	4057		
3618	3624		

Remarks: ALLIED CEMENT #15331

Plugged through: CSG


District: 02

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 23 2004

CONSERVATION DIVISION
WICHITA, KS

Signed _____



(TECHNICIAN)

INVOICED

DATE 6-23-04
INV. NO. 2004061775