

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-50003-00-00  
Spot: SWNE Sec/Twnshp/Rge: 34-34S-28W  
3300 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: RHODES Well #: 1  
County: MEADE Total Vertical Depth: 3285 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: PO BOX 8647  
WICHITA, KS 67208

PROD Size: 4.5 feet: 3265 150 SX CMT  
SURF Size: 8.625 feet: 1307 650 SX CMT

\$1106<sup>76</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/15/2004 2:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 3000' & 4 SX CMT. PLUG AT 1330' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 21 2004

Plugging Proposal Received By: STEVE MIDDLETON  
Date/Time Plugging Completed: 06/15/2004 4:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: STEVE MIDDLETON

CONSERVATION DIVISION  
WICHITA, KS

Actual Plugging Report:

PBTD 3250'. SAND TO 3000' & 4 SX CMT. 1ST PLUG PULLED TO 1330' & SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 400' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT. STAYED FULL.


Perfs:

Top	Bot	Thru	Comments
3111	3113		
3061	3063		

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE. RECOVERED 2550' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED  
DATE 6-21-04  
TEL NO. 2004062767

Form CP-3/3