

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-50005-00-00
Spot: SW Sec/Twnshp/Rge: 22-34S-28W
1320 feet from S Section Line, 1370 feet from W Section Line
Lease Name: BOHLING Well #: 1
County: MEADE Total Vertical Depth: 3210 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

PROD Size: 4.5 feet: 3210 WITH 150 SX CMT
SURF Size: 8.625 feet: 1245 WITH 650 SX CMT

\$104³³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/16/2004 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 2900' WITH 4 SX CMT. PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 21 2004

Plugging Proposal Received By: STEVE MIDDLETON
Date/Time Plugging Completed: 06/16/2004 4:00 PM

Witness Type: PARTIAL
KCC Agent: STEVE MIDDLETON

CONSERVATION DIVISION
WICHITA, KS

Actual Plugging Report:

SAND TO 2900' WITH 4 SX CMT. 1ST PLUG PULL TO 1300' & SPOT 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 400' & SPOT 40 SX CMT. 3RD PLUG PULL TO 40' & SPOT 10 SX CMT.


Perfs:

Top	Bot	Thru	Comments
2982	2988		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2530' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED
DATE 6-21-04
WFL NO. 2004061267

Form CP 2/3