

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-073-19389-00-01  
Spot: NENENE Sec/Twnshp/Rge: 17-23S-11E  
4753 feet from S Section Line, 378 feet from E Section Line  
Lease Name: MCGILVRAY A Well #: W 5  
County: GREENWOOD Total Vertical Depth: 2027 feet

Operator License No.: 32025  
Op Name: GREENWOOD RESOURCES L.L.C.  
Address: PO BOX 847  
PRATT, KS 67124

PROD Size: 6.625 feet: 1932  
SURF Size: 8.25 feet: 1617

*\$65<sup>88</sup>*

Well Type: EOR UIC Docket No: E02466.23 Date/Time to Plug: 05/10/2004 8:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: BERT SANDBURG Company: Phone: (620) 770-1274

Proposed  
Plugging  
Method:

50' CEMENT PLUG AT 1900', 50' CEMENT PLUG AT 1000', 150' CEMENT PLUG TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL  
Date/Time Plugging Completed: 05/11/2004 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

RAN TUBING TO 1953', PUMPED 15 SACKS CEMENT, SHOT CASING AT 900', AND 200'. RAN TUBING TO 900', PUMPED 20 SACKS CEMENT, PULLED TUBING TO 185', PUMPED 45 SACKS CEMENT TO SURFACE, GEL SPACERS BETWEEN CEMENT PLUGS.

Perfs:

Top	Bot	Thru	Comments
1930	2024		

RECEIVED  
KCC District #3

JUN 15 2004

Shandte KCC

Remarks: CORRECTED TO GPS LOCATION

Plugged through:

District: 03

RECEIVED  
JUN 18 2004  
KCC WICHITA

Signed Mike Heffern  
(TECHNICIAN)

INVOICED

DATE 6-18-04  
INV. NO. 2004061751