

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20267-00-01  
Spot: NWSE Sec/Twnshp/Rge: 11-34S-28W  
1831 feet from S Section Line, 1918 feet from E Section Line  
Lease Name: DAVIS RANCH OWWO Well #: 1-94  
County: MEADE Total Vertical Depth: 6043 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: PO BOX 8647  
WICHITA, KS 67208

CIBP Size: feet: 3150  
MSCC Size: feet: 3448 WITH 130 SX CMT  
PROD Size: 4.5 feet: 6012 WITH 125 SX CMT  
SURF Size: 8.625 feet: 1464 WITH 375 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2004 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: JOE MAAS Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 2950' & 4 SX CMT. PLUG AT 1450' WITH 50 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT. 15 SX GEL FOR GEL SPACER.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 21 2004

Plugging Proposal Received By: STEVE DURRANT  
Date/Time Plugging Completed: 06/14/2004 12:15 PM

Witness Type: COMPLETE (100%)  
KCC Agent: STEVE MIDDLETON

CONSERVATION DIVISION  
WICHITA, KS

Actual Plugging Report:

PBTD 5961'. SAND TO 2950' & 4 SX CMT. 1ST PLUG PULL TO 1470' & PUMP 15 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 700' & PUMP 40 SX.CMT. 3RD PLUG PULL TO 40' & PUMP 10 SX CMT. STAYED FULL.


Perfs:

Top	Bot	Thru	Comments
5820	5840		
3012	3020		
2994	3000		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2600' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed \_\_\_\_\_

*[Handwritten Signature]*  
(TECHNICIAN)

INVOICED  
DATE 6-21-04  
INV. NO. 2004061767

*[Handwritten Signature]*  
Form CP-3/3