

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 207
WICHITA, KANSAS 6720

API Well Number: 15-159-03808-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 6-21S-6W
3217 feet from S Section Line, 4275 feet from E Section Line
Lease Name: WILHAUS Well #: 2-6
County: RICE Total Vertical Depth: 3480 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 4.5 feet: 3473 100 SX CMT
SURF Size: 8.625 feet: 165 125 SX CMT *# 113¹⁰*

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2004 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,420' & top with 4 sxs. cement. Shoot casing off. Pull casing to 1,050' & spot 35 sxs. cement. Pull casing to 625' & spot 35 sxs. cement. Pull casing to 250' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: NONE
Date/Time Plugging Completed: 06/11/2004 7:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,420' & topped with 4 sxs. cement. Shot casing off at 1,440'. Pulled casing to 1,036' & spotted 35 sxs. cement w/100# hulls. Pulled casing to 615' & spotted 35 sxs. cement w/200# hulls. Pulled casing to 259' & circulated 100 sxs. cement to the surface.

Perfs:

| Top | Bot | Thru | Comments |
|---|------|------|----------|
| 3473 | 3480 | | |
| RECEIVED KCC DISTRICT #2 JUN 17 2004 WICHITA, KS | | | |

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 21 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE # 24493.

Plugged through: CSG

District: 02

Signed Michael R Wilson
(TECHNICIAN)

INVOICED
DATE 6-21-04
INV. NO. 2004061255