

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21607-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 6-21S-6W  
4914 feet from S Section Line, 2415 feet from E Section Line  
Lease Name: WOLF Well #: C-1  
County: RICE Total Vertical Depth: 3527 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3526  
SURF Size: 8.625 feet: 203 140 SX CMT

*\$114<sup>63</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/14/2004 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 793-2537

Proposed Plugging Method: Sand to 3,410' & top with 4 sxs. cement. Shoot casing off. Pull casing to 1,050' & spot 35 sxs. cement. Pull casing to 625' & spot 35 sxs. cement. Pull casing to 255' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON

Witness Type: PARTIAL

Date/Time Plugging Completed: 06/15/2004 3:00 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,410' & topped with 4 sxs. cement. Shot casing off at 1,816'. Pulled casing to 1,023' & spotted 35 sxs. cement w/100# hulls. Pulled casing to 597' & spotted 35 sxs. cement w/200# hulls. Pulled casing to 256' & circulated 120 sxs. cement to the surface.

Perfs:

Top	Bot	Thru	Comments
3476	3488		
3462	3467		

RECEIVED  
KANSAS CORPORATION COMMISSION  
JUN 21 2004  
CONSERVATION DIVISION  
WICHITA, KS

RECEIVED  
KCC DISTRICT #2  
JUN 17 2004  
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE #24497.

Plugged through: CSG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICED  
DATE 6-21-04  
INV. NO. 2004061755