

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 207
WICHITA, KANSAS 6720

API Well Number: 15-159-20321-00-00
Spot: NWNWNW Sec/Twnshp/Rgc: 6-21S-6W
4779 feet from S Section Line, 4827 feet from E Section Line
Lease Name: WILLHAUS Well #: 3
County: RICE Total Vertical Depth: 3476 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3468 75 SX CMT
SURF Size: 8.625 feet: 207 185 SX CMT

\$ 112⁹⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/11/2004 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,415' & top with 4 sxs. cement. Shoot casing off. Pull casing to 1,050' & spot with 35 sxs. cement. Pull casing to 625' sxs. & spot 35 sxs. cement. Pull casing to 260' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: NONE
Date/Time Plugging Completed: 06/11/2004 11:30 AM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,410' & topped with 4 sxs. cement. Shot casing off at 1,750'. Pulled casing to 1,037' & spotted 35 sxs. cement w/100# hulls. Pulled casing to 616' & spotted 35 sxs. cement w/200# hulls. Pulled casing to 259' & circulated 90 sxs. cement to the surface.

Perfs:

Top	Bot	Thru	Comments
3468	3476		
RECEIVED KCC DISTRICT #2 JUN 17 2004 WICHITA, KS			

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 21 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY COPELAND ACID & CEMENTING. INVOICE #24491.

Plugged through: CSG

District: 02

Signed Michael P. Wilson
(TECHNICIAN)

INVOICED

DATE 6-21-04

INV. NO. 2004061755