

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 207
WICHITA, KANSAS 6720

API Well Number: 15-159-22043-00-00
Spot: NENESW Sec/Twnshp/Rge: 4-19S-6W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ALMQUIST Well #: 4
County: RICE Total Vertical Depth: 3200 feet

Operator License No.: 6141
Op Name: CORONADO OIL & GAS, INC.
Address: PO BOX 1285
GREAT BEND, KS 67530

PROD Size: 4.5 feet: 3168
SURF Size: 8.625 feet: 212

81 104⁰⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2004 10:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Sand to 3,030' & top with 4 sxs. cement. Shoot pipe off. Pull pipe to 900' & spot 35 sxs. cement. Pull pipe to 550' & spot
Plugging 35 sxs. cement. Pull pipe to 265' & circulate cement to the surface.
Method:

**RECEIVED
KCC DISTRICT #2**

JUN 17 2004

WICHITA, KS

Plugging Proposal Received By: JEFF KLOCK

WitnessType: PARTIAL

Date/Time Plugging Completed: 06/09/2004 1:30 PM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Sanded to 3,030' and topped with 4 sxs. cement. Shot pipe off at 1,847'. Pulled casing to 882' & spotted 35 sxs. cement w/200# hulls. Pulled casing to 547' and spotted 35 sxs. cement w/200# hulls. Pulled casing to 252' & circulated 100 sxs. cement to the surface.

**RECEIVED
KANSAS CORPORATION COMMISSION
JUN 21 2004**

CO. REG. DIVISION DISTRICT #2
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING COMPANY, INC. INVOICE #17908.

Plugged through: CSG

District: 02

Signed Michael R. Wilson
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 6-21-04

INV. NO. 2004061759