

6 031187

11-4 X

Jan

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 153-20,096 -00-01

NE NE, SEC. 18, T. 1 S, R. 34 W/E

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5100

Lease Name Sramek Well # 3

Operator: Kern Company

County Rawlins 136.86

Name & Address 3005 N. Big Spring St.

Well Total Depth 4211 feet

Midland, Texas 79705

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 296

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated E-17253

Plugging Contractor Halliburton Services License Number

Address Oberlin, Ks.

Company to plug at: Hour: PM Day: 4 Month: Nov Year: 19 88

Plugging proposal received from E. E. Goodrich

(company name) Kern Co. (phone)

were: 8 5/8" set at 296' w/200 sks. 5 1/2" set at 4199' w/225 sks.

PBTD 4167'. Perf's 4050' - 4152', 4 shots below Dakota at 2240'.

Ordered 50 sks Common Cement. 200 sks 60/40 Poz 8% Gel.

Cement Co. Webb's Water Truck.

RECEIVED  
STATE CORPORATION COMMISSION

12-29-88

DEC 29 1988

Plugging Proposal Received by Carl Goodrich

CONSERVATION DIVISION  
(TECHNICIAN)  
WICHITA, KANSAS

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:15PM Day: 4 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Ran tubing to 4158'. Circulated 50 sks Common Cement

to 3717'. Laid down to 3717, circulated 15 sks gel to 2268'. Laid down tubing

to 2268'. Circulated cement. To surface laid down tubing loaded hole to 8' from

surface. Squeezed backside, 8 5/8" annulus w/50 sks cement to max psi 500%. Blew

out at casing head. Plug complete. Will cut off at casing head and level location.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-5-89

Signed Carl Goodrich (TECHNICIAN)

Carl Goodrich

INV. NO. 23489