

4-032174

E-18,631

API Number: 15-153-20,060-00-00 <sup>01</sup>

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

9-6

NE SW /4 SEC. 14, 01, 34 W  
1980 feet from S section line  
3300 feet from E section line

Operator license# 5552 Lease: Fikan "B" Well # 1W

Operator: Gore Oil Company County: Rawlins

Address: P.O. Box 2757  
Wichita, Kansas 67201-2757  
Well total depth 4325 <sup>140.56</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 324 feet

Aband. oil well\_\_\_, Gas well\_\_\_, Input well X, SWD\_\_\_, D & A\_\_\_

Plugging contractor: Halliburton Services License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 6 Month: September Year: 1996

Plugging proposal received from: Lester Betts

Company: Gore Oil Company Phone: -

Were: Order 400 sxs 60/40 pozmix - 10% gel - 500# hulls.

REGISTERED  
STATE OF KANSAS  
OCT-2 A 12:51  
10-2-96

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 10:30 A.M., Day: 6, Month: September, Year: 1996

Actual plugging report: 8 5/8" set at 324' cwc with 200 sxs. 5 1/2" set at 4201' with 125 sxs. Squeezed at 2000' and 3300' w/800 sxs. Prod. perf. 4105' - 4153'. Squeezed 5 1/2" w/350 sxs cement blend w/500# hulls mixed into Max. P.S.I. 400#. Held. Squeezed 8 5/8" w/50 sxs cement blend to Max. P.S.I. 150#. Held. Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD\_\_\_ BAD\_\_\_ Any plug: YES X NO\_\_\_  
Bottom plug(in place): YES\_\_\_, CALC\_\_\_, NO\_\_\_ Dakota plug: YES X, NO\_\_\_  
Plugged through TUBING\_\_\_, CASING\_\_\_ Elevation: \_\_\_\_\_ GL

I did [ ] / did not [ ] observe the plugging.

Carl Goodrow  
(agent)

INVOICED  
DATE 10-3-96  
INV. NO. 46651