

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00846-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CSE SE

SEC. 35 TWP. 2 RGE. 19 W

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease _____ Dusin _____

Operator The Carter Oil Co Address Box 786 Great Bend, Kans

Field _____ County Phillips

Total Depth 3311 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 262' circulated with cement - 5 1/2" at 3300' with
125 sax cement behind.

Filled with chat to 3285', set 4 sax cement with dump bailer,
puddled 1250' 5 1/2", filled hole with mud to 255', set rock and
15 sax cement, filled with mud to 35', set rock and 10 sax cement
to bottom cellar.

PLUGGING
FILE SEC 35 T 2 R 19 W
BOOK PAGE 117 LINE 15

RECEIVED
STATE CORPORATION COMMISSION
OCT. 16 1951
CONSERVATION DIVISION
Wichita, Kansas

District Conservation Agent
Date 10-14-51

10-16-51