

15-147-00847-00-00

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 120-8

LOCATION Q/11W-SF

SEC. 35 TWP. 2 RGE. 19-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Flores & Hunsie

Operator The Carter Oil Co Address Box #786 - Great Bend - Kansas

Field _____ County Phillips

Total Depth 3365 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 276 ft - Circulated with Cement
5 1/2" casing set at 3364 ft & cemented with 100 sacks Cement
Well had been plugged back from bottom to 3180 ft
Top Preparations 3168 ft - Filled hole with sand to 3160 ft
Set Plug & 5 sacks Cement in 5 1/2" casing at 3160 ft
Shot off & recovered 2500 ft of 5 1/2" casing - Filled with
Mud to 2755 ft - Set Plug & 15 sacks Cement at 2755 ft
Mud to within 30 ft of the
Surface - Plug & 10 sacks Cement.
Best Self - Pipe Puller

C. M. Stough
District Conservation Agent

Date 10-27-47

PLUGGING
FILE SEC 35 T 2 R 19W
BOOK PAGE 170 LINE 8

STATE OF KANSAS
OCT 29 1947
10-29-47