

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-20080-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 10 1969
CONSERVATION DIVISION
Wichita, Kansas
7-10-69

Operator's Full Name Don H. Peaker

Complete Address: Bon Durant Bldg., Pueblo, Colorado 81003

Lease Name Friebo "F" Well No. 1

Location NE SE NW Sec. 35 Twp. 2 Rge. (E) (W) 19

County Phillips Total Depth 3385

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Red Tiger Drlg.

Address: Wichita, Kansas License No.

Operation Completed: Hour 2:30A Day 9 Month 7 Year 1969

The Above well was plugged as follows:
RTD ~~3300~~ 8 5/8 csg set at 200' cwc 150 sk
Gunned pits, circulated heavy mud, set cementing plug and displaced 70 sk cmt thru
drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt. Heavy mud
to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar. Plugged rat
hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED
DATE 7/10/69
INV. NO. 72-w