

DISTRICT CONSERVATION AGENT'S REPORT

15-147-00849-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE
~~CSW NE~~

SEC. 35 TWP. 2 RGE. 19W

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Eltiste

Operator The Carter Oil Co Address Box 786 Great Bend, Kans

Field _____ County Phillips

Total Depth 3368 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 261' circulated with cement - 5 1/2" at 3357' with
125 sax cement behind. Lane Wells plugs to 3189', top perforation
at 3171'.

Filled with chat to 3160', set 4 sax cement with dump bailer,
pulled 1400' 5 1/2", filled hole with mud to 260', set rock bridge
and 15 sax cement, filled with mud to 35', set rock and 10 sax
cement to bottom cellar.

PLUGGING
FILE SEC 35T 2 R 19W
BOOK PAGE 117 LINE 16

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1951
CONSERVATION DIVISION
Wichita, Kansas

10-16-51

James L. ...
District Conservation Agent

Date 10-8-51