

RECEIVED

JUN 07 2004

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION KCC WICHITA WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Greenwood Resources, LLC. Address: P.O. Box 847, Pratt, KS 67124 Phone: (620) 672-6520 x 13 Operator License #: 32025 Type of Well: SWD EOR KCC Bem 6-22-04 Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: (Date) by: (KCC District Agent's Name) Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): List All (If needed attach another sheet) Depth to Top: Bottom: T.D.

API Number: 15-073-19389-00-01 Lease Name: McGilvray A Well Number: W-5 Spot Location (QQQQ): NE-C - NE/4 - 4753 Feet from North South Section Line 378 Feet from East West Section Line Sec. 17 Twp. 23S S. R. 11 East West County: Greenwood Date Well Completed: May 1926 Plugging Commenced: May 7, 2004 Plugging Completed: May 7, 2004

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes a RECEIVED stamp dated JUN 18 2004 from KCC WICHITA.


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU tbg, spot 15 sks cement at 1953'. Shot holes in csg @ 900'. RU tbg, pumped 10 BBLS gel spacer & followed w/ 5 BBLS water spacer. Spot 20 sks cement @ 900'. Pull tbg up to 185', shot holes in csg @ 200'. RU to tbg, break circulation. Mix cement until good returns to surface inside & outside of csg. pulled tbg and filled csg with cement. Used 80 sks 60/40 pozmix 1.5 sks 2% gel, 2 sks Gel spacer.

Name of Plugging Contractor: Greenwood Resources, LLC. License #: 32025 Address: P.O. Box 847, Pratt, KS 67124 JUN 3 2004

Name of Party Responsible for Plugging Fees: Greenwood Resources, LLC. State of Kansas County, Pratt, ss. Chanute, KS

Amy Robertson, Production Clerk (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Amy Robertson, Production Clerk (Address) P.O. Box 847, Pratt, KS 67124

SUBSCRIBED and SWORN TO before me this 25th day of May, 2004. Kevin C. Gates, Notary Public, My Commission Expires: 3/13/08

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

GREENWOOD RESOURCES, LLC.
P.O. BOX 847
PRATT, KS 67124

June 17, 2004

Kansas Corporation Commission
Conservation Division
130 S. Market-Room 2078
Wichita, KS 67202

ATTN: Barbara Montgomery

RE: Plugging Records

Dear Barbara:

Enclosed are the Well Plugging Records that you returned to Greenwood Resources, LLC. The information that was submitted on the forms is all of the information that I have on these wells. When these wells were purchased Greenwood Resources, LLC. received little or no information.

Please let me know if there is something else that I need to do.

Thank you,



Amy Robertson
Production Clerk

RECEIVED
JUN 18 2004
KCC WICHITA