

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R. - 82-3-117

API NUMBER 15-077-30151-00-00

LEASE NAME VALDOISA

WELL NUMBER 1

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 2 TWP. 31 RGE. 8 E W

COUNTY Harper

Date Well Completed 9/22/72

Plugging Commenced 4/23/04

Plugging Completed 23
4/28/04

RECEIVED

MAY 18 2004

KCC WICHITA

TYPE OR PRINT
NOTICE- Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR McCoy Petroleum Corp.

ADDRESS 8080 E Central, Suite 300, Wichita, Ks 67206

PHONE # (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/21/04 (date)

by Steve VanGiesen (KCC District Agent's Name),

Is ACO-I filed? yes If not, Is well log attached? yes

Producing Formation Miss Depth to Top 4423 Bottom 4428 T.D. 4825

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				8 5/8"	25' 329'	none
Production				4 1/2"	4526'	2232'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Quality Well Service, Inc. plugged well as follows: Sand at 4370', bail 4 sacks cement. Pull to 1375', pump 35 sacks cement. Pull to 925', pump 35 sacks cement. Pull to 300', circulate cement to surface with 90 sacks cement. Cut off 8-5/8" covered cellar.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Quality Well Service, Inc. License No. 31925

Address 401 West Main, Lyons, Ks 67554

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES McCoy Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick ss.

Scott Hampel (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott Hampel

(Address) 8080 E Central, Ste. 300, Wichita KS 67206

SUBSCRIBED AND SWORN TO before me this 17th day of May, 20 04

Susan Brady
Notary Public

My Commission Expires 11-4-07

