

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD #4  
K.A.R.-82-3-117

API NUMBER 15-153-20096-00-01

LEASE NAME Sramek

WELL NUMBER 3

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 18 TWP. 1-S RGE. 34 ~~CE~~ or (W)

COUNTY Rawlins

Date Well Completed 11-30-70

Plugging Commenced 11-4-88

Plugging Completed 11-7-88

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Kern Co.

ADDRESS 3005 N. Big Spring St., Midland, TX 79705

PHONE#( 915 683-4832 OPERATORS LICENSE NO. 5100

Character of Well SWD EOR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 25, 1988 (date)

by Mr. Cral Goodrow witnessed the plugging (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing KC Depth to Top 4043' Bottom 4275' est. D. 4211'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing KC	Oil & Water	Surf	296'	8 5/8"	296'	3'
		Surf	4211'	5 1/2"	4211'	3'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Perforated 5 1/2" csg from 2240' to 42' w 4 shots. Ran tubing to 4158' and spotted 50 sx cement on bottom. Pulled tubing to top of cement 3717' and spotted 35 bb1 Halliburton gel at 3717'. Pumped 35 sx 60-40 poz w/8% gel down braden head and filled the 5 1/2" csg to the surface w 150 sx cement down tubing at 2268'. Pulled tbg, filled hole w cement and abandoned well.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. RECEIVED

Address P. O. Box 428, Hays, KS 67601 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kern Co. 11-10-88  
NOV 10 1988

STATE OF Texas COUNTY OF Midland, ss.

William G. Kern (Employee of Operator or Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) William G. Kern

(Address) 3005 N. Big Spring St. Midland, TX 79705



ROBERTA L. BARTLEY  
NOTARY PUBLIC STATE OF TEXAS  
COMMISSION EXPIRES 6-20-89

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 88

Roberta L. Bartley  
Notary Public

My Commission Expires: June 20, 1988