

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME Cahoj Unit

WELL NUMBER 24

SPOT LOCATION 330' FSL & 1650' FEL

SEC. 8 TWP. 1S RGE. 34 (X or W)

COUNTY Rawlins

Date Well Completed 12-12-59

Plugging Commenced 4-18-84

Plugging Completed 4-23-84

15-153-05222-00-02

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Getty Oil Company

ADDRESS 2705 Vine, Unit #4, Hays, Kansas 67601

PHONE # (913) 628-1039 OPERATORS LICENSE NO. 6237

Character of Well Inj.
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist #6

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Lansing-KC Depth to top 3994 bottom 4132 T.D. 4643

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing-KC	Water	3994	4132	10-3/4	360	None
			0A	7	4638	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. MIRU well svc. RIH w/ 126 jts 2-3/8" open ended tbq. Tagged top of fish @ 4042'. Pulled up w/ bottom of tbq @ 4031'. RU Halliburton. Spotted 40 sks 50/50 Poz w/ 6% gel from 4031-3750'. Pulled 15 jts. Ran SLM & found top of cmt @ 3785'. Spotted 132 bbls 9 lb/gal gel from 3777-419'. Circ salt wtr out 7" csg. Pulled 104 jts tbq. Spotted 60 sks 50/50 Poz w/ 6% gel from 419' to surface. Cmt circ out 7" csg. Pulled remain. tbq. Tied onto 10-3/4" bradenhead & pumped 80 sks 50-50 Poz w/ 6% gel w/ 4 sks (over)
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287
Address Box 47, Oberlin, KS 67749

STATE OF Kansas COUNTY OF Ellis, ss.

Frank Renard

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Frank Renard

(Address) 2705 Vine, Unit #4, Hays, KS 67601

RECEIVED
STATE CORPORATION COMMISSION

MAY 03 1984
05-03-1984
CONSERVATION DIVISION
My Commission expires

BOBBIE SCHIPPERS
SUBSCRIBED AND SWORN TO
STATE OF KANSAS
My Appointment Expires:
9-5-84

before me this 2nd day of May, 19 84

Bobbie Schippers
Notary Public

of hulls down annulus. Pumped @ 2 BPM @ 300 psi. No press on backside in 10 min. Well plugged 4-19-84. State plugging agent was notified but did not witness job. Ran SLM on 4-23-84. Tagged up @ 121' inside 7" csg. Filled csg w/ 1 yd. of redi-mix. Cut csg off below ground level, welded steel plate and cleaned up location.