

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Pioneer Exploration LTD
Address: Box 38, Spivey, KS 67142-0038
Phone: (620) 532-5460 Operator License #: 32825
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
MISS. Depth to Top: 4137 Bottom: 4463 T.D. 4290

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-095-10022-00-00
Lease Name: Pomeroy
Well Number: 2-6 KCC BEM 6-21-04
Spot Location (QQQQ): 200' E - NE - SE - NE
3630 Feet from North / South Section Line
560 Feet from East / West Section Line
Sec. 6 Twp. 30 S. R. 8 East West
County: Kingman
Date Well Completed: 09/23/1959 KCC BEM 6-21-04
Plugging Commenced: 6-8-04
Plugging Completed: 6-10-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	318	
				5 1/2	4289	3000

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Dug out 31 joints, checked hole sand, bailed 5 sacks of portland cement, ripped to 3200', no gain, ripped to 3000', worked free pulled to 1300', pumed 35 sacks, pulled to 750', pumped 35 sacks, pulled to 370', circulated to surface with 130 sacks, pulled rest of pipe.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 401 West Main, Lyons, KS 67554

RECEIVED
JUN 21 2004
KCC WICHITA

Name of Party Responsible for Plugging Fees: Pioneer Exploration LTD

State of Kansas County, Kingman, ss.

Don Howard (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Don Howard

(Address) PO Box 38 300W Stanley Spivey KS 67142

SUBSCRIBED and SWORN TO before me this 18th day of June, 2004

Susie Hensiek My Commission Expires: 07/18/2005
Notary Public

SUSIE HENSIEK
NOTARY PUBLIC
STATE OF KANSAS
MY APPT EXP 07/18/05

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

Copy

API # 15 - _____ (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 9/24/59

Well Operator: PIONEER EXPLORATION LTD KCC License #: 32825
(Owner / Company Name) (Operator's)

Address: BOX 38 City: SPIVEY

State: KS Zip Code: 67142-0038 Contact Phone: (620) 532 - 5460

Lease: POMEROY Well #: 2 Sec. 6 Twp. 30 S. R. 8 East West

200' E - NE - SE - NE Spot Location / QQQQ County: KINGMAN

3630 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

560 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 318 Cemented with: 250 Sacks

Production Casing Size: 5 1/2 Set at: 4289 Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4137-63 MISS *Sand 4071 + 55ks*

Rec - 3000

Elevation: 1549 (G.L. / K.B.) T.D.: 4289 P.B.T.D.: 4210 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): AS KCC REQUIERS

RECEIVED

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NOT AVAILABLE TO US

JUN 21 2004
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: DEON HOWARD

Phone: (620) 532 - 5460

Address: BOX 38 City / State: SPIVEY KS 67142-0038

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925
(Company Name) (Contractor's)

Address: 401 W MAIN LYONS KS 67554 Phone: (620) 727 - 3410

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4/30/04 Authorized Operator / Agent: *Deon Howard*
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Quality Well Service, Inc.

Invoice

**401 West Main
Lyons, KS 67554**

Date	Invoice #
6/16/2004	549

Bill To
Pioneer Exploration LTD Box 38 Spivey, KS 67142-0038

P.O. No.	Terms	Lease Name
	net	POMEROY #2

Description	Qty	Rate	Amount
Rig Time	22.5	135.00	3,037.50T
Trucking Floor	1	90.00	90.00T
Sand	1	35.00	35.00T
Cement	5	9.00	45.00T
Ripping Pipe	2	140.00	280.00T
Torch	1	35.00	35.00T
Water Truck	5	60.00	300.00T
Backhoe	2	62.00	124.00T
Phone Calls		7.50	7.50T
Clerical		10.00	10.00T
Wipping Rubber		15.00	15.00T
6-8-04 Drove over rigged up, unset packer, and dug out 31 joints, then packer, gave up, layed tubing down, went in.			
6-9-04 Drove down, sanded bottom, loaded hole, dug cellar out, tore tubing off, and cassing head down, set floor, pulled slips, checked hole sand, bailed 5 sacks of portland cement, ripped 3200', no gain, ripped 3000', worked free, pulled to 1300'.			
6-10-04 Pumped 35 sacks, pulled to 750', pumped 35 sacks, pulled to 370', circulated cement to surface with 130 sacks, pulled rest of pipe, tore down, loaded out, filled cellar in.			
		Subtotal	\$3,979.00
		Sales Tax (6.3%)	\$250.68
		Total	\$4,229.68

**RECEIVED
JUN 21 2004
KCC WICHITA**