

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

15-153-05222-00-02

API Number 15 - - None (of this well)
Lease Owner Getty Oil Company, K.C.C. License No. 6237
Address 2705 Vine Street, Unit #4, Hays, Kansas 67601
Lease (Farm Name) Cahoj Unit Well No. 24
Well Location 330' FSL & 1650' FEL Sec. 8 Twp. 1S Rge. 34 (E) (W) X
County Rawlins Total Depth 4643' Field Name Cahoj
Oil Well Gas Well Input Well X SWD Well Rotary D & A
Well Log attached with this application as required yes
Date and hour plugging is desired to begin Depends on rig availability

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Clinton E. Trego Address P. O. Box 457, Trenton, NE 69044

Plugging Contractor Halliburton Services License No. 5287

Address Box 47, Oberlin, KS 67749

Invoice covering assessment for plugging this well should be sent to:

Name Getty Oil Company

Address 2705 Vine Street, Unit #4, Hays, Kansas 67601

and payment will be guaranteed by applicant or acting agent.

Signed: Frank Renard
Applicant or Acting Agent

Date: October 21, 1983

RECEIVED
STATE CORPORATION COMMISSION
10-26-1983
OCT 26 1983
CONSERVATION DIVISION
Wichita, Kansas

15-153-05222-00-01

OPERATOR Getty Oil Company LEASE NAME Cahoj #24 SEC. 8 TWP. 1S. RGE. 34W

FILL IN WELL LOG AS REQUIRED:

Show all reports of tests of permeability and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay & sand	Surface	371		
Shale	371	525	Tops	
Shale & shells	525	1910	Fort Hays	1450
Shale, Pyrite & Sand	1910	2491		
Shale	2491	2650		
Shale & shells	2650	2850	Permian	2672
Shale	2850	2927		
Anhydrite	2927	2961	Stone Corral	2927
Shale	2961	3502		
Lime & shale	3502	4455	Admire	3606
			Topeka	3780
			Heebner	3922
			Leavenworth	3926
			Lansing	3974
			Marmaton	4272
			Cherokee	4404
Lime	4455	4643	Cherokee Sand	4494
			Cherty Conglomerate	4584
			Mississippian	4608
			Pre-Cambrian	
			Quartzite	4637
Total Depth	4643			

Set 10-3/4" casing at 367' w/300 sx. regular cement.
 Set 7" casing at 4643' w/300 sx regular cement.
 Perforations: 4584'-4610'; 4211'-4220'; 4175'-4178'
 Tested for 8 hours for 97.38 BO, no water.
 Dually completed as SWDW through perms 4584'-4610'.
 Later additional perforations: 3994-3999 and 4128'-4132'.

STATE OF KANSAS RECEIVED
 10-26-1983
 OCT 26 1983
 CONSERVATION DIVISION
 WICHITA, KANSAS



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

October 27, 1983

JOHN CARLIN
MICHAEL LENNEN
R. C. (PETE) LOUX
PHILLIP R. DICK
JUDITH MCCONNELL
BRIAN J. MOLINE

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE SECRETARY
GENERAL COUNSEL

THIS NOTICE
JAN 27 1983
EXPIRES

WELL PLUGGING NOTICE

Cahoj Unit #24
330 FSL 1650 FEL SEC. 8-1-34W
Rawlins Co., Ks.
4643'
Halliburton Services

15-153-05222-00-01

Getty Oil Company
2705 Vine Street, Unit #4
Hays, Ks. 67601

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Yours very truly,

Carol J. Larson, Administrator

Please submit your proposal for plugging the above captioned well to

KCC/KDHE Dist. #6, 1014 Cody, Hays, Ks. 67601, 913-628-1200
seven days prior to plugging the well (KAR-82-3-113)