

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

RECEIVED
STATE CORPORATION COMMISSION
10-24-88
OCT 24 1988

API NUMBER 15-15320096-00-01 (of this well) 6/89
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Kern Co. OPERATORS LICENSE NO. 5100

ADDRESS 3005 N. Big Spring St., Midland, TX 79705 PHONE # (915) 683-4832

LEASE (FARM) Sramek WELL NO. 3 WELL LOCATION C NE/4 NE/4 COUNTY Rawlins

SEC. 18 TWP. 1-S RGE. 34 (E) or (W) (W) TOTAL DEPTH 4211' PLUG BACK TD 4167'

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. C-17253

SURFACE CASING SIZE 8 5/8" SET AT 296' CEMENTED WITH 200 SACKS

CASING SIZE 5 1/2" SET AT 4199' CEMENTED WITH 225 SACKS

PERFORATED AT 4147 to 4152, 4046 to 4050

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Perforate 5 1/2' casing at 2125': Run Tubing & spot 50 sx cement on bottom, pull tubing

to approximately 3700' spot 15 sx Halliburton gel, pull tubing to 2125' pump 45 sx cement down

bradenhead, Circulate hole full of cement.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As mutually agreed, November, 1988

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dave Michaelis PHONE # (308) 345-4988

ADDRESS P. O. Box 85, McCook, NE 69001

PLUGGING CONTRACTOR Halliburton Cementing LICENSE NO. 5287

ADDRESS P. O. Box 428, Hay, KS 67601 PHONE # (913) 625-3431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: William J. Cru
(Operator or Agent)

(4) Kern Co.
3005 N. Big Spring St.
Midland, TX 79705 DATE: Oct 20 1988



Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
MARGALEE WRIGHT	COMMISSIONER
JUDITH McCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI M. FEIST, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

THIS NOTICE

October 25, 1988

JAN 25 '89

WELL PLUGGING NOTICE

15-153-20096-00-01

EXPIRES

Sramek #3 (SWD)
 C NE/4 NE/4
 Sec. 18-01S-34W
 Rawlins County

Kern Company
 3005 N. Big Spring Street
 Midland, TX 79705

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

 Shari Feist
 Director
 State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 268-1200