

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Decatur County, Sec. 6 Twp. 2 Rge. 26 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner C-G Drilling Co.

Lease Name Schwab Well No. 1

Office Address 107 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-1 1954

Application for plugging filed 12-1 1954

Application for plugging approved 12-1 1954

Plugging commenced 12-1 1954

Plugging completed 12-1 1954

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production -- 19--

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation -- Depth to top -- Bottom -- Total Depth of Well 3757 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	187.56	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 180'; set plug; 1/2 sack hulls, 15 sacks cement. Filled hole with mud to 40'; set plug then filled to top with 10 sacks cement, 1/2 sack hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.
Address 107 Rule Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway


(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of December, 1954

My commission expires June 17, 1957

Barbara Donaldson
Notary Public.



12-7-54

CONTRACTOR'S WELL LOG

OPERATOR C-G Drilling Co. FARM NAME Schwab #1
 LOCATION NW NW SW, Sec. 6-2-26W
 POOL NAME Wildcat COUNTY Decatur STATE Kansas
 COMMENCEMENT DATE November 22, 1954 COMPLETION DATE December 1, 1954

LOG OF WELL

Elevation: 2568 R.B.

All measurements from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	187	Sand-Shale		
187	1000	Sand-Shale		
1000	1560	Sandy Shale	0° - 1500'	
1560	1640	Limy-Shale		
1640	2025	Sand-Red Bed	0° - 2000'	
2025	2059	Anhydrite		
2059	2190	Shale-Shells		
2190	2450	Lime-Shale		
2450	2695	Lime-Shale	0° - 2500'	
2695	2825	Lime-Shale		
2825	2945	Lime-Shale		
2945	3060	Lime-Shale	0° - 3000'	
3060	3200	Shale-Lime		
3200	3300	Lime-Shale		
3300	3360	Lime-Shale		
3360	3393	Lime-Shale		DST 3366-93
3393	3421	Lime-Shale		
3421	3445	Lime		
3445	3505	Lime-Shale	0° - 3500'	
3505	3572	Lime-Shale		
3572	3618	Lime-Shale		
3618	3725	Lime-Shale		
3725	3757	Granite Wash		

CASING LEFT IN HOLE AFTER COMPLETION

Ran 187.56' of 8-5/8" Surface Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) ss.


The undersigned certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By J. J. Hallway

Subscribed and sworn to before me this 6th day of December, 1954.

My commission expires: June 17, 1957

Barbara Donaldson
Notary Public

12-7-54