

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-081-21338-00-00

15-081-21388-00-00

LEASE NAME Federal B

RECEIVED

JUN 08 2004

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

633⁶⁶³ Ft. from S Section Line

1986 Ft. from E Section Line

SEC. 8 TWP. 27 RGE. 33 (W or W)

COUNTY Haskell

Date Well Completed 4-2-01

Plugging Commenced 5-7-04

Plugging Completed 5-11-04

LEASE OPERATOR Oxy USA, Inc

ADDRESS 1701 N. Kansas PO Box 2528 Liberal, KS. 67905

PHONE (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5-7-04 (date)

by Richard Lacy (KCC District Agent's Name)

Is ACO-1 filed? yes If not, is well log attached? no

Producing Formation Morrow Depth to Top 5112 Bottom 5135 T.D. 5400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Surf</u>			<u>1757</u>	<u>8 5/8</u>	<u>1757</u>	<u>-</u>
<u>Prod</u>			<u>5400</u>	<u>5 1/2</u>	<u>5400</u>	<u>2032</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from feet to feet each s
Mixed 400 lb. hulls & 25 5x cmt. to plug perfs from 5112 to 4912. Shot &
pulled 5 1/2 to 1780. Circ. hole w/mud mixed 50 5x 1780 to 1630
30 5x 800 to 700 10 5x 40 to 0 Cut off & capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS.


STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well, as filed the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 4th day of June, 2004



Kathleen Poulton
Notary Public

My Commission Expires: November 8, 2006