

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-009-15454-00-00

API NUMBER N/A
 LEASE NAME Eveleigh B *see*
 WELL NUMBER 3 *see*
990 Ft. from S Section Line
3300 Ft. from E Section Line
 SEC. 5 TWP. 18 SRGE. 12 (E) or (W)
 COUNTY Barton
 Date Well Completed 5/24/61
 Plugging Commenced 6/10/04
 Plugging Completed 6/10/04

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Nadel and Gussman, L.L.C.
 ADDRESS 15 E. 5th St., Suite 3200, Tulsa, OK 74103
 PHONE#(918) 583-3333 OPERATORS LICENSE NO. 32638
 Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/20/04 (date)
 by Dennis Hamel (Pat Staab was on job) (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes
 Producing Formation Arbuckle Depth to Top 3343 Bottom 3350 T.D. 3350

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Depleted	0	215	8-5/8	215	None
		0	3346	5-1/2	3346	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
 Circ hole w/tbg w/6 its to clear bridge. Perforated 2 holes @ 1301' & 725'. Ran tbg to 3240'. Mixed 15 sks gel followed by 35 sks 60/40 10% gel and 200# hulls. Pulled tbg to 1320'. Mixed 175 sks 60/40 10% gel w/500# hulls and circ cement to surface both 5-1/2 & 8-5/8. Shut backside and mixed 20 sks. Pressured to 300#. Pulled tbg. Hooked to csg. Mixed 20 sks & pressured to 150#. SIP - 100#

Name of Plugging Contractor Steve's Well Service Inc. Allied Cementing *KCC Part witness compl. BE 6/24/04* License No. N/A 32983 *KCC 6/24/04*
 Address P.O. Box 31, Russell, KS 67605

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman, L.L.C.
 STATE OF Oklahoma COUNTY OF Tulsa, ss.

M.R. Taylor, Manager of Production (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Mr Taylor
 (Address) 15 E. 5th St., Suite 3200, Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 2004

Kathy Cannon
 Notary Public

My Commission Expires: 8-1-07

RECEIVED
 JUN 24 2004
 KCC WICHITA

WELL LOG

Date started 5-17-61
Date completed 5-24-61

Eveleigh B-3
C-N₂ SE SW Section 5, Twp. 18, Range 12W
Barton County, Kansas

	Elevation	1812*	KB
		1809*	DF
		1806*	GL
Set 215* of 8 5/8" 32# surface casing cemented with 150 sacks of posmix cement.	Anhydrite	706*	
	Topeka	2830*	(+1018)
Set 5 1/2" OD, 15#SS range 2, 8 rd. thread used casing at 3346*, 4* off bottom, with 115 sacks of regular cement.	Heebner shale	2984*	(+1172)
	Brown Lime	3084*	(+1272)
	Lancing KC	3100*	(+1288)
	Arbuckle dolomite	3343*	(+1531)
	Total depth	3350*	

- 0* = 215* Clay
- 215* = 315* Shale and shells
- 315* = 500* Shale and sand
- 500* = 706* Shale, shells and red bed
- 706* = 715* Anhydrite
- 715* = 1340* Shale and shells
- 1340* = 3140* Lime and shale
- 3140* = 3350* Lime

AFFIDAVIT

State of Kansas County of Barton

I A. M. Jones, certify that the above is a true and correct log as reflected by the daily drilling reports of the Jones Drilling Company.

By: A. M. Jones
A. M. Jones

Subscribed and sworn before me this 2nd day of June, 1961.

John W. Poos
John W. Poos Notary Public

My commission expires April 11, 1963.

RECEIVED
JUN 24 2004
KCC WICHITA