

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-159-22421-0000
LEASE NAME Wellman Ranch
WELL NUMBER No. 3

TYPE OR PRINT

NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.

1980 Ft. from South Line of Section
330 Ft. from West Line of Section

LEASE OPERATOR RAMA Operating Co., Inc. SPOT LOCATION W/2 Nw Sw
ADDRESS P.O. Box 159 Section 28 Township 21s Range 9w
CITY, STATE, ZIP Stafford, Kansas 67578 County Rice
PHONE # 620-234-5191 Date Well Completed June 22, 2004
Character of Well Dry and Abandoned Date Plugging Commenced June 22, 2004
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed June 22, 2004

The plugging proposal was approved on 06/22/04 (date)
by Steve VanGieson (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 3536

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands	Water sands	0	180	and		
Redbeds	Shale/Siltstone	180	242	8-5/8"	238	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Received plugging orders 6/22/04 from Steve VanGieson. Plugged using 130 sx of 60/40 Poz; 6% Gel.

Heavy mud in hole and between all plugs. Bottom plug @ 1300'/35sx; 2nd plug @ 900'/35sx; 3rd plug

@ 290'/35sx; top plug at 60'/10 sx cemented to surface. Plugged rathole/15sx; no mousehole.

Plug down at 1:15 pm, 6/22/04. Allied ticket # 17914. Reported to KCC 6/22/04.

Name of Plugging Contractor Sterling Drilling Company

Licence No. 5142

Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RAMA Operating Co., Inc. (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*
(Gary M. Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 23rd day of June, 2004



Pamela S. Fields
(Notary Public)

My Commission Expires: _____

RECEIVED
JUN 24 2004
KCC WICHITA

Sterling Drilling Company, Rig #1

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Wellman Ranch No. 3

LOCATION: W/2 Nw Sw
API: 15-159-22421-0000

Section 28 T 21s R 9w
Rice County, Kansas

OWNER: RAMA Operating Co., Inc.
CONTRACTOR: Sterling Drilling Company, Rig #1

COMMENCED: 16-Jun-04
COMPLETED: 22-Jun-04

TOTAL DEPTH: DRILLER 3536 FEET
LOGGER No Logs FEET

Ground Elevation: 1689
KB Elevation: 1698

LOG

0 -	15 FEET	Top Sand
15 -	25 FEET	Clay
25 -	72 FEET	Sand and Gravel
72 -	296 FEET	Redbeds and Shales
296 -	315 FEET	Anhydrite (Driller's)
315 -	1250 FEET	Shales and Salt
1250 -	3536 FEET	Limestone/Shale and Dolomite

CASING RECORDS

Surface/Production Casing Data:

Spud at 3:45 pm on 06-16-04. Drilled 12 1/4" hole to 242'. Ran 6 joints of new 23#, 8-5/8" surface casing. Talled 242' set at 238' KB. Cemented with 225 sacks 70/30 Poz, 2% Gel, 3% CC. Cement did circulate. Plug down at 10:15 pm on 06-16-04 by Allied Cementing. Ticket # 13005.

Plugging Data:

Received plugging orders 6/22/04 from Steve VanGieson. Plugged using 130 sx of 60/40 Poz; 6% Gel. Heavy mud in hole and between all plugs. Bottom plug @ 1300'/35sx; 2nd plug @ 900'/35sx; 3rd plug @ 290'/35sx; top plug at 60'/10 sx cemented to surface. Plugged rathole/15sx; no mousehole. Plug down at 1:15 pm, 6/22/04. Allied ticket # 17914. Reported to KCC 6/22/04.

DEVIATION SURVEYS

1/2 degree(s) at 242 feet
2-1/4 degree(s) at 3536 feet

RECEIVED
JUN 24 2004
KCC WICHITA