

6040316

15-147-00719-0000  
R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

75WCNE-NE, SEC. 35, T. 2 S, R. 19 (W)

— feet from S section line  
— feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5064

Lease Name Dayton Well # 5

Operator: Sierra Plt. Co. Inc.

County Phillips 111.32

Name & Address 211 N. Broadway

Well Total Depth 3425 feet

Box 247

Conductor Pipe: Size feet

Wichita, KS 67202

Surface Casing: Size 8 1/2" feet 312' w/ 200

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Entg. License Number

Address Russell, Kansas

Company to plug at: Hour: 9:00 AM Day: 15 Month: 1 Year: 19 85

Plugging proposal received from Norman Redie

(company name) Sierra Plt. (phone)

were: 4 1/2" csg set @ 3423' w/ 100 sx cmt. - Perfs @

3176' ↔ 3365' - Hole in csg @ 785-800' lg @

800' & below - (Anky. approx - 1500') -

Ordered 500 sx 50 poz, 10% gel, w/ 1/4" flo-ceil & 6 sx hulls.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:45 AM Day: 15 Month: 1 Year: 19 85

ACTUAL PLUGGING REPORT

amped in csg (4 1/2") → 250 sx cmt. w/ 4 sx hulls

1050 # MAX. P.S.I., 850 # Shut-in P.S.I.

amped in S.P. → 200 sx cmt. w/ 2 sx hulls

350 # MAX. P.S.I., 100 # Shut-in P.S.I.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

T-29-85  
6736

Signed Dennis L. Hamel (TECHNICIAN)