

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00953-00-00
Spot: CSESE Sec/Twnshp/Rge: 35-2S-19W
660 feet from S Section Line, 735 feet from E Section Line
Lease/Unit Name: DAYTON WFU Well Number: 17
County: PHILLIPS Total Vertical Depth: 3370 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

Conductor Pipe: Size feet: \$109.53
Surface Casing: Size 8.625 feet: 317 200 SX CMT
Production: Size 4.5 feet: 3370 100 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/05/2002 10:00 AM

Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.

Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing leak - fluid level 140' from surface.
Perfs 3114' - 3302'. PBTD 3339'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/05/2002 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Rigged up Western Well Service. Ran tubing to 2500'.
Allied pumped 130 sxs 60/40 pozmix - 10% gel with 400# hulls.
Cement circulated. PTOH.
Allied squeezed with 120 sxs - OH - cement 20' down.
Hooked up to backside. Allied pumped 50 sxs cement with 100# hulls.
Max. P.S.I. 200#. S.I.P. 100#.

RECEIVED
JUL 10 2002
KCC WICHITA 7-15-02

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams
(TECHNICIAN)

INVOICED

DATE 7-18-02
INV. NO. 2003060041

Form CP-2/3

JUL 10 2002

35-2-19W

HUMBLE OIL & REFINING #17 DAYTON UT (TWN) APP C SE SE

Contr. BUICK DRLG PHILLIPS County

E_2038RB Comm. 9-29-61 IP 20 BOPD/LANS

Tops	Depth	Datum
HEEB	3099	-1061
TOR	3122	-1084
LANS 'A' ZN	3141	-1103
'B' ZN	3177	-1139
'D' ZN	3195	-1157
'E' ZN	3213	-1175
'G' ZN	3231	-1193
'H' ZN	3270	-1232
'I' ZN	3290	-1252
'J' ZN	3306	-1268
'K' ZN	3331	-1293
ID	3370	-1332

Casing
8" 317
4" 3370

PERF 12/3114-17; 8/3122-24; ACID 1500;
8/3133-35; ACID 750; 8/3170-72; ACID 500;
20/3185-90; ACID 1500; 20/3203-08; 20/
3211/13; ACID 2500; 8/3226-28; ACID 750;
12/3261-64; ACID 1000; 16/3282-86; ACID
1250; 8/8800-02; ACID 750; PMP 20 BO &
15 BW

DAYTON POOL

-	-	-	-
-	-	-	-
-	-	-	-
-	-	-	-

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS