

6040183

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-147-20,456-00-00  
SEC. 26, T. 2 S, R. 19 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 9500

Operator: Nova Petroleum Corp.  
Name & Address: P.O. BOX 11630  
Salt Lake City, Ut. 84147

feet from N/S section line  
feet from W/E section line

Lease Name Krafft Well # 1

County Phillips

Well Total Depth 3513 122.96 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 256 w/160 sks

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling License Number 5302

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 13 Month: September Year: 19 84

Plugging proposal received from Sam Wagganer

(company name) Red Tiger (phone) \_\_\_\_\_

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk hulls and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XX

Operations Completed: Hour: 4:45 PM Day: 13 Month: September Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 1625 w/40 sks

2nd plug @ 1100 w/100 sks w/1 sk hulls

3rd plug @ 260 w/40 sks

4th plug @ 40' w/10 sks

10 sks in Rat Hole

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 17 1984  
9-17-84  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Cemented by Halliburton (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-26-84 observe this plugging.

DATE 9-26-84

INV. NO. 3856

Signed Dennis L. Hamel SH (TECHNICIAN)