

4-071137

2-24

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,342 -00-00

C SW NW /4 SEC. ²⁵26, 02 S, 19 W
3300 feet from S section line
4620 feet from E section line

Operator license# 5134 Lease Kaiser well # 1

Operator: Graham-Michaelis Corporation County Phillips

Address: P.O. Box 247 Well total depth 3588 feet
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet
Norman Rodie Surface pipe 8 5/8 Inch @ 270 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 24 Month: February Year: 95

Plugging proposal received from: Norman Rodie - Leon Kuhn

Company: Graham-Michaelis Corporation Phone: 316-264-8394

Were: 8 5/8" - 270' S.P. cwc. w/200 sxs. 4 1/2" casing set @ 3585'
w/175 sxs. cement. Perfs. 3288' - Elv. 2157' - Anhy. 1630'. 4 1/2"
casing squeeze @ 2600' w/300 sxs. cement. Proposal 300 sxs. 60/40 pozmix
8% gel - 5 sxs. hulls. Pumpe in with pump truck.

1) Perforate 4 1/2" casing at 1650' and 1150'.
2) Pump in 4 1/2" casing - load top to bottom with hulls mixed in - shut
under pressure.

3) Squeeze 4 1/2" x 8 5/8" annulus with cement - shut in under pressure.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00A.M., Day: 24, Month: February, Year: 95

Actual plugging report: Graham Michaelis ordered 300 sxs. 60/40 pozmix -
and 5 sxs. hulls. Pumped in with pump truck.

1) Perforate 4 1/2" casing at 1650' and 1150'.
2) Pumped in 4 1/2" casing with 15 sxs. cement followed with 285 sxs.
cement with 5 sxs. added.

3) Squeezed 4 1/2" x 8 5/8" annulus - P.S.I. 500# - did not take cement.

4) 02-27-95 cement top 600' - filled 4 1/2" casing to top with 3 yards
Redi-mix.

Remarks: Cemented by Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X. Elevation: 2157 GL

I did X observe the plugging.

Marion J. Schmidt
(agent)

Form CP-2/3

INVOICED

DATE 3-14-95

INV. NO. 42252

2-24

RECEIVED
STATE CORPORATION COM
MAR 13 1995
3-13-95
CONSERVATION DIVISION
WICHITA, KANSAS