

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-20224-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 25-2S-19W
4290 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: KAISER Well Number: 1
County: PHILLIPS Total Vertical Depth: 3533 feet

Operator License No.: 3077
Op Name: JOHNSON OIL
Address: 258 HWY 36
PHILLIPSBURG, KS 67661

Conductor Pipe: Size feet:
Surface Casing: Size 8.62 feet: 216 170 SX CMT
Production: Size 4.5 feet: 3577 200 SX CMT 8/14.82
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/09/2001 8:00 AM
Plug Co. License No.: 3077 Plug Co. Name: JOHNSON OIL
Proposal Rcvd. from: KEVIN JOHNSON Company: JOHNSON OIL Phone: (785) 543-6171

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/09/2001 1:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

RU Cementers to 8 5/8" S.P.
Squeezed 50 sxs cement with 100# hulls mixed in cement.
Max. P.S.I. 300#. S.I.P. 200#.
RIH with tubing to 1800'.
RU Cementers to 2 3/8" tubing - spotted 100 sxs cement with 400# hulls mixed in cement.
P.O.O.H. with tubing.
Squeezed 4 1/2" casing with 100 additional sxs cement.
Max. P.S.I. 400#. S.I.P. 300#.

INVOICED
DATE 6-14-01
INVOICE NO. 2001061936

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 13 2001
CONSERVATION DIVISION

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Dennis L. Hamel
(TECHNICIAN)

MAY 30 2001

