

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-039-20026-00-00

NOV 6 1967

11-6-67

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Braden Drilling, Incorporated.  
Complete Address 1620 Wichita Plaza, Wichita, Kansas.  
Lease Name Powell Well No. 1  
Location CSE-SW Sec. 4 Twp. 2 Rge. (E) (W) 26  
County Decatur Total Depth 3740'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 9:45 AM Day 2 Month 11 Year 1967

The above well was plugged as follows:

210'--8 5/8" Surface pipe, cement circulated with 100 Sx.  
Dakota section from 1815' to 1650'.

Circulated hole with heavy mud. Pulled DP to 1840' and displaced 100 Sx. cement thru  
DP from 1840' to 1520'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from  
240' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 11/6/67  
INV. NO. 6634-W