

6 090239

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,767-00-00
NE 1/4, SEC. 6, T. 2 S., R. 26 W. 1/4
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5011

Lease Name Kelly Well # 1

Operator: Viking Resources

County Decatur 120.90

Name & Address 217 E. William

Well Total Depth 3720 feet

Wichita, Ks. 67202-4005

Conductor Pipe: Size - feet -

Surface Casing: Size 8 7/8 feet 260

Abandoned Oil Well - Gas Well - Input Well - SWD Well - D&A

Other well as hereinafter indicated -

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420

Address Wichita, Ks. 67202-3484

Company to plug at: Hour: - Day: 25 Month: June Year: 19 85

Plugging proposal received from Judy w/ White & Ellis

(company name) White & Ellis Drilling, Inc. (phone) -

were: Order 205 sks. 50/50 permit, 6% gel, 3% Cal. Cl. & 8 7/8" wear plug, spot all plugs through drill pipe w/ heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All - Part - None

Operations Completed: Hour: 3:45 AM Day: 26 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug 3720' w/ 20 sks.

2nd plug 2050' w/ 20 sks.

3rd plug 1345' w/ 100 sks. & 1 sk. Cellu-Floke

4th plug 310' w/ 40 sks.

5th plug 40' solid bridge 1 sk. shells & 10 sks. 15 sks. in rat hole

Remarks: Elevation - 2592', Anhydrite - 2042', Anhydrite - yes
(If additional description is necessary, use BACK of this form.) (Allud)

INVOICED observe this plugging.

DATE AUG 06 1985

Signed Edwin A. Schumacher
(TECHNICIAN)

INV. NO. 9346

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1985
8-5-85
CONSERVATION DIVISION
Wichita, Kansas