

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21219-00-00
Spot: E2SENE Sec/Twnshp/Rge: 17-25S-9W
3300 feet from S Section Line, 330 feet from E Section Line
Lease Name: WILDIN Well #: 1
County: RENO Total Vertical Depth: 4015 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

PROD Size: 5.5 feet: 4010 150 SX CMT
SURF Size: 8.625 feet: 222 150 SX CMT

130-49

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/12/2004 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: See actual report.

**RECEIVED
KCC DISTRICT #2
JUN 23 2004**

WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 05/12/2004 2:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded perforations to 3816' and put 5 sacks on top. Cut off 5-1/2" casing at 2720'. Pulled casing to 1500' and pumped 35 sacks of cement. Pulled casing to 800' and pumped 35 sacks of cement. Pulled casing to 270' and circulated cement to surface.

60/40 posmix with 4% gel.

Recovered 2720'.

Remarks: ALLIED CEMENT #15322

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 6-25-04

FILE NO. 2004061782