

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 207
WICHITA, KANSAS 6720

API Well Number: 15-159-00508-00-00⁰¹
Spot: NWNWNW Sec/Twnshp/Rge: 16-19S-6W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: SCOTT OWWO Well #: 1
County: RICE Total Vertical Depth: 3584 feet

Operator License No.: 6141
Op Name: CORONADO OIL & GAS, INC.
Address: PO BOX 1285
GREAT BEND, KS 67530

PROD Size: 4.5 feet: 3263
SURF Size: 8.625 feet: 200

\$116⁴⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2004 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand to 3,005' & top with 4 sxs. cement. Shoot casing off. Pull casing to 900' & spot 35 sxs. cement. Pull casing to 550' & spot 35 sxs. cement. Pull casing to 250' & circulate cement to the surface.

RECEIVED
KCC DISTRICT #2
JUN 17 2004

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 06/09/2004 5:00 PM KCC Agent: MICHAEL WILSON

WICHITA, KS

Actual Plugging Report:

Perfs:

Sanded to 3,000' & topped with 4 sxs. cement. Shot casing off at 2,410'. Pulled casing to 906' & spotted 35 sxs. cement w/200# hulls. Pulled casing to 554' & spotted 35 sxs. cement w/200# hulls. Pulled casing to 289' & circulated 100 sxs. cement to the surface.

RECEIVED
KANSAS CORPORATION COMMISSION
JUN 21 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING COMPANY, INC. INVOICE #17909.

Plugged through: CSG

District: 02

Signed

Michael R Wilson

(TECHNICIAN)

INVOICED

DATE 6.25.04
INV. NO. 2004061780